



At A Glance

Project:

Provision of Maintenance
Dredging Works at THF-PIY
Wharf Front.

Client:

THHE Fabricators Sdn Bhd

Contract Sum:

RM 1,325,025.00

Contract Period:

15.10.2020—25.11.2020

P115 : Dredging Works at Tabung Haji Wharf Front.

Dredging Works

The THHE yard is fully equipped and ready for offshore and onshore fabrication work located on Pulau Indah.

The project aims to carry out maintenance dredging to keep the depth of the seabed for a safe passage so that ships and boats can access 'in' or 'out' from THHE Pulau Indah Fabrication Yard.

Design Parameters:

| | |
|----------------------------|---------------------------------------|
| Design Depth | : -4.0mCD |
| Disposal Location Distance | : 17 nautical miles |
| Dredge Quantity | : 11,390 m ³ (Provisional) |

Vessel Deployed:

| No. | Equipment | Capacity | Quantity |
|-----|----------------------------------|---------------------|----------|
| 1 | Grab Dredger | 16m ³ | 1 |
| 2 | Non-propelled Split Hopper Barge | 1,000m ³ | 2 |
| 3 | Tug Boat | 1,000bhp & 1,200bhp | 2 |
| 4 | Anchor Handling Tug | 5T | 1 |

