



At A Glance

Project:

Maintenance Dredging Works at Pulau Ketam Public Jetty.

Client:

Propetco Sdn Bhd

Contract Sum:

RM 473,637.50

Contract Period:

05.02.2021—11.02.2021

P117 : Dredging Works at Pulau Ketam Jetty.

Dredging Works

The Pulau Ketam Public Jetty at Port Klang serves the travel needs of daily ferry commuters and tourists between the mainland and Pulau Ketam.

The project is intended to deepen and widen the navigation channel within the required of depth at Pulau Ketam Jetty, Port Klang (within area of 117m x 30.6m).

Design Parameters:

Design Depth	: -4.0mCD
Disposal Location	: 1 nautical miles
Dredge Quantity	: 7,405 m ³

Vessel Deployed:

No.	Equipment	Capacity	Quantity
1	Grab Dredger	13m ³	1
2	Self-propelled Split Hopper Barge	1,000m ³	1
3	Non-propelled Split Hopper Barge	1,000m ³	1
4	Tug Boat	1,000bhp	1
5	Anchor Handling Tug	5T	1

