



At A Glance

Project:

Maintenance Dredging Works at Wharf B5 to B24 Westport, Klang, Selangor.

Client:

Integrated Marine Works

Contract Sum:

RM 3,290,000.00

Contract Period:

23.04.2021—28.06.2021

P118 : Maint. Dredging at Wharf B5 to B24 Westport, Klang.

Dredging Works

Being the Top 10 most connected port in the world, Westports is able cater for cargo to be transported to any part of the world. The project is intended to carry out maintenance dredging by broadening its product base, including through 'logistical integration' and increasing its attractiveness to a wider range shippers and shipping lines.

Design Parameters:

Design Depth	: 15mCD
Disposal Location Distance	: 12 nautical miles
Dredge Quantity	: 150,000 m ³ (Provisional)

Vessel Deployed:

No.	Equipment	Capacity	Quantity
1	Grab Dredger	13m ³	1
2	Self-propelled Split Hopper Barge	1,000m ³	1
3	Non-propelled Split Hopper Barge	1,000m ³	2
4	Tug Boat	1,000bhp & 1,200bhp	3
5	Anchor Handling Tug	5T	1

